


BRUHAT BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE


Office of the Executive Engineer, Dasarahalli Division

Schedule-B

Name of Work:-Re Construction of drains at Sampangi Ramaiah layout in Ward No 14


SI	Description of Item	Unit	Qty	Sanctioned Estimate Rates	
				In Figures	In words (Rs)
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	Cum	99.00	90.72	Rupees Ninety & Seventy two Paise Only
2	Removing B.S.Slab of drain and stacking etc.,	Sqm	356.40	50.11	Rupees Fifty & Eleven Paise only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	103.95	4211.38	Rupees Four Thousand Two hundred Eleven & Thirty eight Paise only
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	48.68	4690.50	Rupees Four Thousand Six hundred Ninety & Fifty Paise only
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete	Sqm	356.40	70.04	Rupees Seventy & Four Paise only
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick	Sqm	237.60	343.44	Rupees Three hundred forty three & Forty four Paise only
7	Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	Sqm	528.00	924.48	Rupees Nine hundred twenty four & Forty eight Paise only


EXECUTIVE ENGINEER-2
SAMPANGI RAMAIAH LAYOUT, DASARAHALLI DIVISION
BANGALORE - 560 010


EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-56

8	Supplying and fixing precast reinforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	594.00	1600.00	Rupees One thousand Six hundred only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	99.00	78.24	Rupees Seventy Eight & Twenty four Paise only


EXECUTIVE ENGINEER-2
 BRIDG, BBMP Division
 BANGALORE - 560 010


EXECUTIVE ENGINEER
 Executive Engineer
 Bruhat Bangalore Mahanagara Palike,
 Dasarahalli Division
 Dasarahalli Zone, Bangalore-57.

Signature of the Contractor

Executive Engineer.